



MANIFOLD KIT PART NO. SCK015



	ITEM NO.	QTY	PART NO.	DESCRIPTION
	1	1	B04720	BRACKET, SC77XE MANIFOLD
	2	3	1735	FITTING, ELBOW
	3	1	1750	FITTING, PUSH ON TUBE
	4	1	1751	TUBING, PLY COIL 1/4" O.D.
	5	1	64-2213	SWIVEL, STANLEY
	6	2	1736	PIN, CLEVIS w/ E-CLIP
	7	1	B04033	MANIFOLD, SC TOOL
	8	1	1124	PLUG, HEX SOCKET 1/4-18 NPT
OB	9	2	TL710220	S.H.C.S. #10-24 x 1 1/4"
~®				

- 1. REMOVE 1/8 NPT PRESSURE PLUG FROM SIDE OF HOUSING.
 2. INSTALL ELBOW FITTING (#2) WITH SEALANT INTO HOUSING USING A 12mm WRENCH
 3. REMOVE BOTH #10 FASTENERS HOLDING SIDEPLATES ONTO THE HOUSING.
 4. REMOVE 1/4 FASTENER FROM END CAP (SEE DIAGRAM).
 5. MOUNT MANIFOLD BRACKET (#1) ONTO TOOL BETWEEN MAGAZINE AND HOUSING, USING FASTENERS (#9) AND THE EXITING NUTS.
 6. INSTALL 1/4-18 NPT PLUG (#8) INTO BOTTOM OF TOOL HANDLE WITH SEALANT.
 7. VERIFY ALL TUBES ARE PRESSED INTO FITTINGS COMPLETELY.
 8. ATTACH TO AIR SUPPLY AND CHECK FOR AIR LEAKS.

SC77 MANIFOLD 6/14/04 REV. "C" CHANGED ITEM 9 WAS TL710120 & REMOVED ITEM 10 SC77 MANIFOLD 5/5/04 REV. "B" ADDED ITEMS 9 & 10



- 1. REMOVE 1/8 NPT PRESSURE PLUG FROM SIDE OF HOUSING.
 2. INSTALL ELBOW FITTING (#2) WITH SEALANT INTO HOUSING USING A 12mm WRENCH
 3. REMOVE BOTH #10 FASTENERS HOLDING SIDEPLATES ONTO THE HOUSING.
 4. REMOVE 1/4 FASTENER FROM END CAP (SEE DIAGRAM).
 5. MOUNT MANIFOLD BRACKET (#1) ONTO TOOL BETWEEN MAGAZINE AND HOUSING USING ITEM #9 FASTENERS AND THE EXISTING NUTS.
 6. INSTALL 1/4-18 NPT PLUG (#8) INTO BOTTOM OF TOOL HANDLE WITH SEALANT.
 7. VERIFY ALL TUBES ARE PRESSED INTO FITTINGS COMPLETELY.
 8. ATTACH TO AIR SUPPLY AND CHECK FOR AIR LEAKS.

SC7 MANIFOLD 6/14/04 REV. "B" ADDED ITEM #9 SC7 MANIFOLD 8/15/02 REV. "A"